REVISED QUOTATION FOR THE PROPOSED HOUSE TO BE BUILT FOR "Andrew" .

S/N	ITEM	QUANTIT Y	UNIT COST	TOTAL COST
A.	FOUNDATION/WAL L			
1.	Hard core	3trips	50,000/=	150,000/=
2.	Aggregates	2trips	120,000/	240,000/=
3.	Bricks	10,000	150/=	1,500,000/=
4.	River sand	5trips	150,000/	750,000/=
5.	Pit sand	8trips	50,000/=	400,000/=
6.	Cement	108bags	26,000/=	2,808,000/=
7.	Twisted bars	10 pieces	27,000/=	270,000/=
8.	Ring wires	30 pieces	4,000/=	120,000/=
9.	Binding wires	7kgs	7,000/=	49,000/=
10.	Timber for ring beam	20 pieces	20,000/=	400,000/=
11.	Iron/twisted nails - 4 inches - 6 inches - 3 inches - 2 inches	1 kg 1 kg 1 kg ¹ / ₂ kg	5,000/= 5,000/= 5,000/= 5,000/=	20,000/=
	Sub-total			6,707,000/=
B.	ROOFING			
1.	Iron sheets (Cover max)	30 pieces	40,000/=	1,200,000/=
2.	Timbers	1,500 feet	200/=	300,000/=
3.	Nails - 6 inches - 5 inches - 4 inches	6kgs 4kgs 4kgs 3kgs	5,000/= 5,000/= 5,000/= 5,000/=	30,000/= 20,000/= 20,000/= 15,000/=
	- 3 inches	2kgs	6,000/=	12,000/=

	- 2 inches			
4.	Roofing nails	5kgs	6,000/=	30,000/=
5.	Hooping iron	32 pieces	1,500/=	48,000/=
6.	Doors	2 pieces	200,000/	400,000/=
7.	Windows	4 pieces	100,000/	400,000/=
C.	PAINTING			
1.	Under coat	2 Jerrycans	70,000/=	140,000/=
2.	Weather guard	2 Jerrycans	90,000/=	180,000/=
3.	Transport			450,000/=
4.	Labour			1,300,000/=
	Sub-total			4,545,000/=
	Grand-Total			11,252,000/ =